

## Note to Reviewer.

These 30% design plans were prepared based upon the published FEMA 100-Year base flood elevation of 10.0 NAVD. As discussed in Section 4.2 of the *Smith Canal Closure Structure Early Implementation Program Project Report,* the 100-Year and 200-Year flood elevations for Smith Canal have been recently recalculated to be 9.4 and 9.5 respectively. The design plans will be revised at the 60% design stage to reflect the latest design water surface elevations.

# San Joaquin Area

# Flood Control Agency SMITH CANAL CLOSURE STRUCTURE PRELIMINARY DESIGN FOR CONDITIONAL LETTER OF MAP REVISION

30% DESIGN NOT FOR CONSTRUCTION **JANUARY** 29, 2010

SAN JOAQUIN AREA FLOOD CONTROL AGENCY:

JAMES GIOTTONINI Date

**RECLAMATION DISTRICT 1614** 

EXECUTIVE DIRECTOR

Christopher Neudeck Date

RECLAMATION DISTRICT 828

Thomas Rosten Date



WARNING: CONTRACTOR TO USE EXTREME CAUTION. EXACT DEPTH AND LOCATION OF UNDERGROUND UTILITIES ARE UNKNOWN. CONTRACTOR TO FIELD VERIFY LOCATIONS AND DEPTH OF EXISTING UTILITIES PRIOR TO CONSTRUCTION AND SHALL NOTIFY ENGINEER OF ANY CONFLICT. CONTRACTOR SHALL CALL USA AT 1—800—227—2600 AT LEAST TWO WORKING DAYS BEFORE DIGGING.


HDR ENGINEERING:

Keith DE Lapp, RCE No. C48214 HDR Engineering


PBI ENGINEERING:

Finbarr J O'Regan, RCE No. C57527 Date PBI Engineering

<u>U</u>	UTILITY CONTACT INFORMATION			
UTILITY	REPRESENTATIVE	PHONE		
GAS				
DRAINAGE				
TELEPHONE				
ELECTRICITY				
WATER				
SEWER				
FIRE				
TELEVISION				
TELEPHONE				
U.S.A.				



LOCATION MAP



VICINITY MAP

PETERSON . BRUSTAD . INC

1180 Iron Point Rd. Suite 260 Folsom, CA 95630 PH: (916)608-2212 Fax: (916)608-2232



FESSION	REV	DATE	BY	DESCRIPTION
F. DE TO				
\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\				
Z				
48214				
6-30-10 /20//				
\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\				
FCALIFOR	-		_	



SMITH CANAL CLOSURE STRUCTURE PRELIMINARY DESIGN FOR CONDITIONAL LETTER OF MAP REVISION

TITLE SHEET

SAN JOAQUIN AREA FLOOD CONTROL AGENCY G-001 DESIGNED BY: K. DE LAPP SIGNATOR'S NAME COMPANY NAME

SHEET

XX

SHEET INDEX

### MECHANICAL:

M-001 GENERAL MECHANICAL NOTES
M-401 CONTROL BUILDING MECHANICAL PLAN AND SECTION

M-501 CONTROL BUILDING MECHANICAL DETAILS
M-502 CONTROL GATE MECHANICAL DETAILS

#### NOTES:

1. BOLD SHEETS INCLUDED IN CURRENT 30% PLAN SET.

PETERSON . BRUSTAD . INC ENGINEERING . CONSULTING 1180 Iron Point Rd. Suite 260 Folsom, CA 95630 PH: (916)608–2212 Fax: (916)608–2232



87 F. P. S.	PROFESSIONAL FEE	
REGIST KA	No. 48214 Exp. 6-30-10	
1/2	CIVIL ORNE	

DATE

BY DESCRIPTION



SMITH CANAL CLOSURE STRUCTURE
PRELIMINARY DESIGN FOR CONDITIONAL
LETTER OF MAP REVISION

SAN JOAQUII	N AREA FLOOD	CONTROL AGE	NCY	G-002
SCALE: NO SCALE	CHECKED BY:	[	DATE:	OF.
DESIGNED BY: K. DE LAPP				
DRAWN BY: V. RUSSO				xx
CHECKED BY:				
DATE:	SIGNATOR'S NAME,	COMPANY NAME		SHEETS

SHEET INDEX

-002

SHEET



CENTERLINE, CLASS, CLOSE



EXTERIOR, EXTERNAL, EXTENSION



7	REV	DATE	BY	DESCRIPTION
1				
NE NE				
]]				
//				
	_		_	

HERTZ, CYCLES PER SECOND



### **SMITH CANAL CLOSURE STRUCTURE** PRELIMINARY DESIGN FOR CONDITIONAL LETTER OF MAP REVISION

# SAN JOAQUIN AREA FLOOD CONTROL AGENCY

SIGNATOR'S NAME COMPANY NAME


SHEET

G-003 ÓF DESIGNED BY: K. DE LAPP **ABBREVIATIONS** DRAWN BY: V. RUSSO XX CHECKED BY:

DATE:

1180 Iron Point Rd. Suite 260


PH: (916)608-2212 Fax: (916)608-2232













SAN JOAQUI	N AREA FLOOD COI	VIROL AGE
SCALE: NO SCALE	CHECKED BY:	
DESIGNED BY: K. DE LAPP		
DRAWN BY: V. RUSSO		
CHECKED BY:		

DATE:

**LEGEND & SYMBOLS** 

XX SIGNATOR'S NAME COMPANY NAME SHEETS

#### BASIS OF DESIGN

- 1. BASIS OF DESIGN UTILIZED FOR THIS DRAWING SET IS INCLUDED IN THE FOLLOWING STATEMENT:
  - A. THE PURPOSE OF THE DESIGN CONCEPT PRESENTED IN THIS DRAWING SET IS TO FURTHER DEVELOP THE FEASIBILITY OF THE SWITH CANAL CLOSURE STRUCTURE CONCEPTUALIZATION PRESENTED IN THE TECHNICAL MEMORANDUM, DATED JUNE 27, 2008, IN SUPPORT OF AN APPLICATION FOR A CONDITIONAL LETTER OF MAP REVISION TO BE FILED WITH FEMA.
- 2. GEOTECHNICAL INFORMATION USED FOR THIS DRAWING SET WAS PROVIDED BY KLEINFELDER, INC. IN THE FOLLOWING DOCUMENT:
  - A. GEOTECHNICAL SERVICES REPORT, SMITH CANAL CLOSURE STRUCTURE, STOCKTON, CALIFORNIA, DATED APRIL 9, 2008.
- THE DESIGN WATER SURFACE ELEVATION USED TO ESTABLISH THE TOP OF SHEET PILE WALL ELEVATION WAS PROVIDED BY PETERSON BRUSTAD, INC. IN THE FOLLOWING DOCUMENT:
  - A. SMITH CANAL CLOSURE CONCEPTUALIZATION TECHNICAL MEMORANDUM, FOR THE SAN JOAQUIN AREA FLOOD CONTROL AGENCY, DATED JUNE 27, 2008.
- 4. THE PRELIMINARY TOPOGRAPHIC FEATURE INFORMATION USED IN THE DEVELOPMENT OF THE DESIGN FEASIBILITY SHOWN IN THIS DRAWING SET WAS PROVIDED BY KJELDSEN, SINNOCK & NEUDECK, INC. AND IS A COMPILATION OF AVAILABLE AERIAL AND FIELD DATA.
- 5. EXPERIENCE AND JUDGMENT WERE APPLIED IN THE DEVELOPMENT OF THIS DESIGN CONCEPT WHERE PROJECT SPECIFIC DATA OR GUIDANCE IS UNAVAILABLE.
- THE PERFORMANCE OF EARTHEN LEVEE SYSTEMS IS NOT PART OF THE DESIGN FEASIBILITY PRESENTED IN THIS DRAWING SET.
- RIGHT-OF-WAY CONSTRAINTS WERE NOT CONSIDERED IN THE DEVELOPMENT OF THIS DESIGN CONCEPT.
- 8. UTILITY RESEARCH AND IDENTIFICATION WAS NOT PERFORMED AS PART OF THE DEVELOPMENT OF THIS DESIGN CONCEPT.

CONTRACT REPRESENTATIVES				
PUBLIC / UTILITY SERVICE	RESPONSIBLE ENTITY	REPRESENTATIVE	TELEPHONE	
UNDERGROUND ALERT	USA		800-227-2600	
AGENCY	SJAFCA			
AGENCY (O&M)	RD 1614			
AGENCY (O&M)	RD 828			
DESIGN ENGINEER	HDR	SAM PLANCK	916-817-4700	
GEOTECHNICAL ENGINEER	KLEINFELDER, INC.		916-366-2347	
HABITAT MANAGER				
NATURAL GAS	PACIFIC GAS AND ELECTRIC CO.			
ELECTRICITY	PACIFIC GAS AND ELECTRIC CO.			
TELEPHONE	AT&T			
SEWER/WATER/DRAINAGE	CITY OF STOCKTON			
CONSTRUCTION MANAGER				
TRANSPORTATION	CITY OF STOCKTON			

#### NOTE:

ADMINISTRATION OF ALL WORK PERFORMED BY THE CONTRACTOR SHALL COMPLY WITH THE GENERAL SPECIFICATIONS.

PETERSON . BRUSTAD . INC ENGINEERING . CONSULTING	
1180 Iron Point Rd. Suite 260 Folsom, CA 95630 PH: (916)608–2212 Fax: (916)608-	




	PROFESSIONAL PROFE
REGIS	No. 48214 Exp. 6-30-10
11/3	CIVIL ORNE

		CIOC
		San Joaquin Free FLOOD CO
		010
	_	

DATE BY DESCRIPTION

LETTER OF MAP REVISION  GENERAL NOTES
SMITH CANAL CLOSURE STRUCTURE PRELIMINARY DESIGN FOR CONDITIONA

				SHEET			
AL	SAN JOAQUIN AREA FLOOD CONTROL AGENCY						
	SCALE: NO SCALE	CHECKED BY:	DATE:				
		CHECKED BI.	DATE	ÓF			
	DESIGNED BY: K. DE LAPP						
	DRAWN BY: V. RUSSO			xx			
	CHECKED BY:						
	DATE:	SIGNATOR'S NAME, COMPANY	NAME	SHEETS			



CHECKED BY: DATE:

SIGNATOR'S NAME COMPANY NAME

ALIGNMENT LINE TABLE								
LINE NO.	LENGTH	DIRECTION	START POINT (N,E) END POINT (N,E)					
L-1	723.81	S32*15'49"E	2172704.6946, 6315580.13	2172023.84, 6316009.94				
L-2	223.29'	S77*21'54"E	2172023.8400, 6316009.94	2171975.00, 6316227.83				
L-3	582.50'	S65*54'25"E	2171852.7817, 6316581.11	2171614.99, 6317112.87				
L-4	359.75'	S89*23'26"E	2171555.6908, 6317382.38	2171551.86, 6317742.11				
L-5	219.69'	S50°49'57"E	2171551.8644, 6317742.11	2171413.11, 6317912.44				

	ALIGNMENT CURVE TABLE								
CURVE NO.	PI STATION	Δ	RADIUS	TANGENT	LENGTH	CHORD DIRECTION	CHORD LENGTH		
C-1	12+16.45	167'45'13"	1752.31'	187.98	374.54	S70*55'02.35"E	373.82'		
C-2	21+25.53	160'23'11"	810.08	140.02	277.31	S77*35'25.98"E	275.95		

### BASIS OF CONTROL (CITY OF STOCKTON):

BEARINGS AND DISTANCES SHOWN ARE BASED ON THE NORTH AMERICAN DATUM OF 1983 (NAD 83) CONVERTED TO THE CALIFORNIA SYSTEM OF 1983, ZONE 3 (CCS83—111) AS REFERENCED BY THE CITY OF STOCKTON HORIZONTAL CONTROL SYSTEM (1991.35 EPOCH DATE). GRID DISTANCES SHOWN MUST BE MULTIPLIED BY 1.00005782 (CALCULATED AT POINT 1003) TO OBTAIN GROUND DISTANCES. ELEVATIONS SHOWN ARE BASED ON THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD 88) AS REFERENCED BY AVAILABLE CITY OF STOCKTON BENCHMARKS (COS 96 ADJUSTMENT) 2003 REVISION. UNITS SHOWN ARE BASED ON THE US SURVEY FOOT.



1180 Iron Point Rd. Suite 260 Folsom, CA 95630 PH: (916)608–2212 Fax: (916)608–2232 HDR Engineering Inc.




7	REV	DATE	BY	DESCRIPTION	
[h:					
GINEE					
(B)					
.//					
//					
	-		_		


	F
Son Jooquin free ROOD CONTROL Reency	
Sar Audum reed Production Indiana	


SMITH CANAL CLOSURE STRUCTURE
PRELIMINARY DESIGN FOR CONDITIONAL
LETTER OF MAP REVISION


TOPOGRAPHIC SURVEY/
ALIGNMENT CONTROL No. 1
ALIGNMENT CONTROL NO. 1


			SHEET				
SAN JOAQUIN AREA FLOOD CONTROL AGENCY							
ALE: AS NOTED	CHECKED BY:	DATE:	OF				
SIGNED BY: K. DE LAPP							
RAWN BY: V. RUSSO			xx				
IECKED BY:							
TE:	SIGNATOR'S NAME,	COMPANY NAME	SHEETS				
·							

















NOTE:

SEE SHEET S-301 FOR STRUCTURAL DETAILS OF STEEL SHEET PILES.

PETERSON . BRUSTAD . INC
ENGINEERING . CONSULTING

1180 Iron Point Rd. Suite 260
Folsom, CA 95630
PH: (916)608-2212 Fax: (916)608-2232


HDR Engineering Inc.



ESSION	REV	DATE	BA	DESCRIPTION	
. DE TO					
\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\					
48214 (7) 5-30-10					So
5-30-10					-
111/2011					
CALIFOR	_		_		

	r
SIOCCO	
A Joaquin Firea FLOOD CONTROL Rgency	
No.	

SMITH CANAL CLOSURE STRUCTURE RELIMINARY DESIGN FOR CONDITIONAL LETTER OF MAP REVISION	SAN JOAQUIN AREA FLOOD CONTROL AGENCY		
TYPICAL SHEET PILE SECTIONS	SCALE: 3/16" = 1' - 0" DESIGNED BY: K. DE LAPP DRAWN BY: V. RUSSO CHECKED BY:		OF XX
	DATE:	SIGNATOR'S NAME COMPANY NAME	SHEETS




HDR Engineering Inc.

XX

DRAWN BY: V. RUSSO
CHECKED BY:
DATE:


SIGNATOR'S NAME, COMPANY NAME



HDR Engineering Inc.

CHECKED BY: DATE:

SIGNATOR'S NAME, COMPANY NAME



CHECKED BY: DATE:

SIGNATOR'S NAME, COMPANY NAME



PLAN 1" = 10'



1180 Iron Point Rd. Suite 260 Folsom, CA 95630 PH: (916)608–2212 Fax: (916)608–2232 HDR Engineering Inc.




OROFESS/ON	KEV	DATE	101	DESCRIPTION
F. DE				
( Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z				
No. 48214 (Fig. 6-30-10 (Fig. 6)				
(2)				
CIVILAR				
OF CALIFO	_		_	
	$\overline{}$		_	


SINFCA	SMITH CANAL CLOSURE STRUCTURE PRELIMINARY DESIGN FOR CONDITIONAL LETTER OF MAP REVISION

SHEET PILE	
TIE-IN AT LUIS PARK BOAT LAUNCH	

			SHEET
SAN JOAQUII	N AREA FLOOD	CONTROL AGENCY	C-404
SCALE: AS NOTED	CHECKED BY:	DATE:	OF
DESIGNED BY: K. DE LAPP			
DRAWN BY: V. RUSSO			xx
CHECKED BY:			
DATE:	SIGNATOR'S NAME,	COMPANY NAME	SHEETS




# TYPICAL EXTERIOR BUILDING SLAB CORNER DETAIL



THICK "T"	REINFORCMENT
6"	#4 @ 12" EA WAY
8"	#5 @ 12" EA WAY

NOTE: ELIMINATE 2-INCH SAND LAYER WHERE MOISTURE BARRIER IS NOT REQUIRED.

#### TYPICAL BUILDING SLAB-ON-GRADE NTS




#### NOTES:


- 1. PROVIDE BROOM FINISH UNO PER THE REQUIREMENTS OF SPEC SECTION 03002.
- PROVIDE TOOLED JOINTS AT 5 FOOT CENTERS IN PERPENDICULAR DIRECTIONS.
   PROVIDE 6" CLASS 2AB UNDER CONCRETE SIDEWALKS AND LANDINGS, UNLESS OTHERWISE NOTED.
- 4. PROVIDE 12" CLASS 2AB UNDER CONCRETE PAVEMENT AND RAMPS
- 5. #5 @ 8" OC EW AT MID-DEPTH AT CONCRETE PAVEMENT AND RAMPS.
- 6. 8" THICKNESS AT CONCRETE PAVEMENT AND RAMPS
- 7. LEAN CONCRETE WITH MINIMUM 28 DAY COMPRESSIVE STRENGTH F'c=3,000 PSI MAY BE USED AT CONCRETE SIDEWALKS AND LANDINGS ONLY.
  SEE SPECIFICATION SECTION 03002 FOR ADDITIONAL INFORMATION.

### CONCRETE SIDEWALK AND RAMP DETAIL






# TYPICAL SLAB-ON-GRADE DEPRESSION (FOR ONE LAYER OF REBAR)




- 1. WALL REINFORCEMENT NOT SHOWN FOR CLARITY.
- 2. FOR ALL REINFORCEMENT SEE PLANS.


## TYPICAL WALL HORIZ CONST JOINT JOINT AT PIPE INTERFERENCE



# TYPICAL BUILDING SLAB EDGE




## TYPICAL HOUSEKEEPING PAD DETAIL




#### NOTES:

- FOR NEW EQUIPMENT PADS ON EXISTING SLABS, DRILL INTO EXISTING SLAB TO AT 12" CENTERS AROUND PERIMETER OF EQUIPMENT PADS AND SET #5 HOOKED DOWELS IN EPOXY GROUT.
- FOR EQUIPMENT PADS ON NEW SLABS, PROVIDE #5 DOWELS AT 12" CENTERS AROUND PERIMETER OF EQUIPMENT BASE.
- EQUIPMENT DIMENSIONS SHALL BE AS INDICATED ON THE DRAWINGS OR AS DETERMINED BY THE EQUIPMENT MANUFACTURER AND APPROVED
- 4. EQUIPMENT BASES SHALL BE INSTALLED LEVEL. TOLERANCE IS 1/16".
- 5. WHERE CONCRETE SLAB THICKNESS WILL NOT PROVIDE MINIMUM COVER AS SPECIFIED ON DWGS, PROVIDE EXTRA THICKNESS OF CONCRETE.
- 6. SIZE PADS PER PLAN WHEN SHOWN.

# EQUIPMENT PAD DETAIL



# CONCRETE CURB



FOUIPMENT BASE

- PROVIDE PAD UNDER ELECTRICAL AND MECHANICAL EQUIPMENT WEIGHING MORE THAN 5000 POUNDS, SUPPORTED ON GRADE, UNLESS NOTED OTHERWISE ON
- EQUIPMENT BASE DIMENSIONS SHALL BE AS INDICATED ON THE DRAWINGS OR AS DETERMINED BY THE EQUIPMENT MANUFACTURER AND APPROVED BY THE
- ANCHOR BOLTS AS RECOMMENDED BY THE EQUIPMENT MANUFACTURER. BOLTS SHALL BE HELD IN POSITION WITH A TEMPLATE WHILE EQUIPMENT BASE IS BEING CAST.
- PIPE SLEEVES SHALL BE USED TO PROVIDE THE ANCHOR BOLT A MINIMUM MOVEMENT OF 1/2" IN ALL DIRECTIONS. MINIMUM SLEEVE LENGTH SHALL BE 8 TIMES THE BOLT DIAMETER. SLEEVES SHALL BE FILLED WITH NON—SHRINK GROUT. PIPE SLEEVES SHALL HAVE A MINIMUM INTERNAL DIAMETER 1" GREATER THAN BOLT DIAMETER AND A MAXIMUM INTERNAL DIAMETER OF 3" GREATER
- 5. EQUIPMENT BASES SHALL BE INSTALLED LEVEL. TOLERANCE IS 1/16".

ISOLATED EQUIPMENT PAD DETAIL

**SMITH CANAL CLOSURE STRUCTURE** 

PETERSON . BRUSTAD .	INC	
ENGINEERING . CONSULTING	(	

1180 Iron Point Rd. Suite 260 Folsom, CA 95630 PH: (916)608-2212 Fax: (916)608-2232





OROFESS/ON	REV	DATE	BY	DESCRIPTION
ESTAF. DE TO				
No. 48214				
No. 48214   m   20     Exp. 6–30–10   m				
(v)				
1 1 1 1 1 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0				
FOF CALIFOR	-		_	




PRELIMINARY DESIGN FOR CONDITIONAL LETTER OF MAP REVISION

**TYPICAL CONCRETE DETAILS I** 


	SHEET
SAN JOAQUIN AREA FLOOD CONTROL AGEI	S-002
SCALE: NO SCALE CHECKED BY:	E: OF
DESIGNED BY: K. DE LAPP	
DRAWN BY: V. RUSSO	xx
CHECKED BY:	
DATE: SIGNATOR'S NAME, COMPANY NAME	SHEETS

- SLAB AND WALL REINFORCEMENT NOT SHOWN. TERMINATE ALL SLAB AND WALL REINFORCING 2" CLEAR TO EDGE OF EXPANSION JOINT.
- 2. THICKEN SLAB ONLY WHERE SLAB THICKNESS IS GREATER THAN 1'-0"







#### NON-WATER BEARING SLAB OR WALL



WATER BEARING SLAB OR WALL








#### DETAIL "B" - SOIL-SIDE

- 1. FOR WALLS, FORM ALL JOINT EDGES AT 1/2" CHAMFER.
- 2. FOR UNDER SIDE OF EXPOSED SLABS, FORM JOINT EDGES AT 1/2" CHAMFER.
- 3. FOR SLABS, PROVIDE 1/4" RADIUS TOOLED EDGES AT TOP SURFACE
- 4. USE DETAIL  ${\rm "B"}$  AT UNDERSIDE OF SLABS ON GRADE ONLY. USE DETAIL "A" AT ALL OTHER LOCATIONS.
- 5. "W" = 1" WIDE UNLESS OTHERWISE INDICATED ON THE DRAWINGS.
- 6. SMOOTH DOWEL AND PVC ASSEMBLY AT EXPANSION JOINTS SHALL USE GREENSTREAK "SPEED DOWEL" NO. PSD12/#7TX (BASE CODE PSD/#7BX).

# EXPANSION JOINT (EJ)









### DOWELLED CONSTRUCTION JOINT (DSJ)

- 1. ANY ONE OF THE DETAILS ABOVE MAY BE USED AT LOCATIONS INDICATED ON DRAWINGS AS "SJ," AT CONTRACTOR'S OPTION.
- 2. WHERE "DSJ" IS INDICATED ON PLAN, THE "DSJ" SHALL BE USED.





ROUGHEN CONSTRUCTION JOINT

 SEE SPECIFICATION FOR REQUIREMENT TO TIE WATERSTOPS IN PLACE TO PREVENT MOVEMENT OR FOLDING OVER. CONSTRUCTION JOINT (CJ




## ADDITIONAL REINFORCEMENT AT RE-ENTRANT SLAB CORNER







FLAT CROSS

VERTICAL CROSS






FLAT TEE



VERTICAL TEE



FLAT ELL

## VERTICAL ELL

CHECKED BY

DATE:

- BULB TYPE WATERSTOPS SHALL BE HANDLED SIMILAR TO AS SHOWN WITH BULB JOINTS MITERED FOR FULL CONTINUITY OF HOLLOW BULB.
- ONLY STRAIGHT BUTT JOINT WELDS AE ALLOWED IN THE FIELD

SHOP FABRICATED WATERSTOP





1180 Iron Point Rd. Suite 260 Folsom, CA 95630 PH: (916)608-2212 Fax: (916)608-2232





DROFESS/OA	REV	DATE	BY	DESCRIPTION
LEOTH F. DE				
15/2				
(四 No. 48214 開)				
\\\\^\C\\\\ Exp. 6-30-10 \\\\^\z\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\				
\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\				
AY CIVIL OF				
OF CALIFE	-		-	




**SMITH CANAL CLOSURE STRUCTURE** PRELIMINARY DESIGN FOR CONDITIONAL LETTER OF MAP REVISION

**TYPICAL CONCRETE DETAILS II** 

SAN JOAQUII	N AREA	FLOOD CONTROL A	GENCY	S
SCALE: NO SCALE	CHECKED	BY:	DATE:	1
DESIGNED BY: K. DE LAPP			·	
DRAWN RY: V RUSSO				1

SHEET S-003 SIGNATOR'S NAME COMPANY NAME



#### NOTES:

NTS

ALTERNATE PROJECTION AS SHOWN


1. "S" = BAR SPACING INDICATED ON THE DRAWINGS

HORIZONTAL WALL JOINTS

WITH WATERSTOP

2. FOR HORIZONTAL REINF BAR LOCATION RELATIVE TO VERTICAL REINF BAR LOCATION (INSIDE OR OUTSIDE) SEE DRAWING (INSIDE SHOWN).


REINFORCING SPACING CALLED OUT ON DRAWINGS



#### NOTES:


- 1. ALL HOOKS SHALL BE STD 90 DEGREE HOOKS.
- 2. SEE DRAWINGS FOR ADDITIONAL HORIZONTAL BARS. STAGGER BETWEEN TYPICAL REINF SPACING, EXTEND TO 1/5 OF DISTANCE TO NEAREST ADJACENT WALL IN EACH DIRECTION, UNO
- 3. OPTIONAL LAP LOCATION. APPLIES TO BOTH DOUBLE AND SINGLE LAYER CONDITIONS TYP.

## WALL REINFORCEMENT AT **CORNER & INTERSECTIONS**




# STAGGERED REINFORCING AT CONSTRUCTION JOINT

# AT CONSTRUCTION JOINT








## RECTANGULAR OPENING DETAIL

### CIRCULAR OPENING DETAIL


- PROVIDE ADDITIONAL REINFORCING THE SAME SIZE AS DISCONTINUOUS REINFORCEMENT AT
  OPENING. QUANTITY OF REINFORCING IN EACH DIRECTION SHALL BE EQUAL TO OR ONE
  GREATER THAN THE NUMBER OF DISCONTINUOUS BARS. PLACE 1/2 OF ADDITIONAL
  REINFORCING BARS EACH SIDE OF OPENING, PLACE ADDITIONAL REINFORCEMENT AT 3" OC
  (TYPICAL BOTH DIRECTIONS AND ALL LAYERS OF REINFORCEMENT). START FIRST BAR 2" CLEAR
  TO OPENING.
- EXTEND ADDITIONAL REINFORCING BEYOND EDGE OF OPENING AS SHOWN ABOVE. ADDITIONAL BARS MAY TERMINATE AT THE END OF THE WALL WITH A STANDARD HOOK WHERE THE LENGTH OF THE WALL WILL NOT PERMIT BARS TO EXTEND AS SHOWN ABOVE.
- TYPICAL WALL OR SLAB REINFORCING NOT SHOWN FOR CLARITY. TERMINATE TYPICAL REINFORCING 2" CLEAR TO OPENING.
- OPENINGS 12" OR LESS IN SLABS AND OPENINGS 18" OR LESS IN WALLS, NO EXTRA REBARS
  ARE REQUIRED UNLESS SHOWN OTHERWISE. TYPICAL REINFORCING SHALL BE RESPACED (NOT CUT) TO ALLOW FOR OPENINGS TO BE MADE.
- 5. UNLESS SHOWN OTHERWISE ON DRAWINGS, PROVIDE EXTRA REINFORCING AROUND OPENINGS AS SHOWN AND INDICATED ABOVE.
- PROVIDE ADDITIONAL DOWELS PER NOTE 1 ABOVE FOR ALL OPENINGS NEAR THE FLOOR SLAB, BASE SLAB, OR CORNERS.

### EXTRA REINFORCING AROUND OPENINGS





- FOR FOOTING REINFORCEMENT AND FOOTING SIZE, SEE FOUNDATION PLAN, SECTIONS AND SCHEDULE.
- 2. "T" DENOTES FOOTING THICKNESS.



TYPICAL CONCRETE BEAM CONSTRUCTION JOINT DETAIL

SHEET

PETERSON . BRUSTAD . INC

OPTIONAL WALL BAR

1180 Iron Point Rd. Suite 260 Folsom, CA 95630 PH: (916)608-2212 Fax: (916)608-2232 HDR Engineering Inc.

-construction joint

- SPLICE LAP LENGTH




PROFESS/ON	REV	DATE	BY	DESCRIPTION
OTH F. DE				
No. 48214				
Exp. 6-30-10 / //				
CIVIL				
FOF CALIFOR	-		-	




TYPICAL CONCRETE DETAILS III

			0
SAN JOAQUII	N AREA FLOOD C	ONTROL AGENCY	S-004
SCALE: NO SCALE	CHECKED BY:	DATE:	ÓF
DESIGNED BY: K. DE LAPP			
DRAWN BY: V. RUSSO			xx
CHECKED BY:			
DATE:	SIGNATOR'S NAME, C	OMPANY NAME	SHEETS


# SPACER FOR WALL REINFORCEMENT



<u>HORIZONTAL POSITION - A VERTICAL POSITION - B</u>



HORIZONTAL AND VERTICAL POSITION - C



#### NOTES:

**WELDED** 

- 1. CHIP, GRIND, OR GOUGE TO SOUND METAL BEFORE WELDING OTHER SIDE.
- 2. USE DETAIL A & B FOR #9 & LARGER BARS. USE DETAIL C FOR #8 & SMALLER BARS. USE DETAIL D FOR #6 & SMALLER BARS.
- 3. E 90 ELECTRODE FOR GRADE 60.
- 4. SEE AWS D1.4 FOR WELDING PROCESS, PREHEAT REQUIREMENTS, AND OTHER DETAILS. SUBMIT WELDING PROCEDURE PER AWS.
- 5. 1 1/2" FOR #3 AND #4 BARS; 2" FOR #5 BARS; AND 2 1/2" FOR #6 BARS

# **LOCATION**

### \* MINIMUM COVER

UNFORMED SURFACES ADJACENT TO EARTH

FORMED OR TOP SURFACES EXPOSED TO WEATHER OR SATURATED AIR, SUBMERGED OR IN CONTACT WITH EARTH:

OTHER LOCATIONS:

BARS IN BEAMS OR GIRDERS, INCLUDING STIRRUPS AND COLUMN SPIRALS OR TIES

SLABS, WALLS AND JOINTS #9 AND LARGER

#8 AND SMALLER


BAR DIA + 1/4"


3"

1 1/2"

\* COVER FOR REINFORCING STEEL SHALL NOT BE LESS THAN THE MINIMUM GIVEN ABOVE (NO MINUS TOLERANCE), AND SHALL NOT EXCEED THE MINIMUM BY MORE THAN 1/4 INCH WHERE THE CONCRETE THICKNESS IS 24" OR LESS, OR MORE THAN 1/2 INCH WHERE THE CONCRETE THICKNESS IS MORE THAN 24 INCHES.

# REINFORCEMENT CONCRETE COVER






TYP. STIRRUP

TYP. COLUMN TIE OR CLOSED STIRRUP

BAR SIZE	R	
#3 TIES & STIRRUPS	2d	
#3-#8	3d	
#9-#11	4d	
#14-#18	5d	




CONCRETE JOINT

BAR SIZE	HL	HW	TL	D	f'c=4.0 OR 4.5 KSI
GRADE 60	'''		,.		Ldh ∗
#3	6"	3"	3"	2 1/4"	6"
#4	8"	4"	4 1/2"	3"	7"
#5	10"	5"	5"	3 3/4"	9"
#6	1'-0"	6"	6"	4 1/2"	10"
#7	1'-2"	7"	7"	5 1/4"	12"
#8	1'-4"	8"	8"	6"	14"
#9	1'-7"	11 3/4"	10 1/2"	9 1/2"	15"
#10	1'-10"	1'-1 1/4"	11 1/2"	10 3/4"	17"
#11	2'-0"	1'-2 3/4"	1'-1"	12"	19"

\* COMPLYING WITH MINIMUM COVER REQUIREMENTS OF ACI 318, 12.5.3. OTHERWISE Ldh MUST BE RE-CALCULATED.

## REINFORCING HOOK **SCHEDULE**



**VERTICAL APPLICATION**  **HORIZONTAL APPLICATION** 

ADHESIVE ANCHOR SCHEDULE						
REINFORC	ING BARS	ANCHOR BOLTS/RODS				
BAR SIZE	EMBED LENGTH (L)	DIA (IN)	EMBED LENGTH (L)			
#3	4*	3/8"	5"			
#4	5"	1/2"	6"			
#5	6"	5/8"	7"			
#6	7"	3/4"	8"			
#7	8"	7/8"	9"			
#8	9"	1"	10"			
#9	10"					
#10	12"					

NOTES: 1. EPOXY TYPE IS SUBJECT TO APPROVAL OF THE ENGINEER OF RECORD.
2. EMBEDMENT LENGTHS SHOWN ARE MINIMUM. PROVIDE MANUFACTURER'S RECOMMENDATIONS FOR INSTALLATION.


## **ADHESIVE** ANCHOR DETAILS & SCHEDULE

	f'c =	5.0 ksi	fy = 6	0.0 ksi
BAR SIZE	LAP LEN	GTH (IN)	EMBEDMENT	LENGTH (IN)
DAR SIZE	TOP	OTHER	TOP	OTHER
#3	21	16	16	12
#4	28	22	22	16
#5	35	27	27	21
#6	43	33	33	25
#7	62	48	48	37
#8	71	55	55	42
#9	80	62	62	47
#10	91	70	70	53
#11	101	77	77	59

#### NOTES:

- 1. LAP LENGTHS SHOWN ARE FOR CLASS "B" TENSION SPLICES.
- 2. LAP LENGTHS AND EMBEDMENTS SHOWN ARE FOR BARS SPACED LATERALLY @ > FIVE TIMES THE BAR DIAMETER AND FOR MINIMUM COVER IN ACCORDANCE WITH ACI 318-95.
- 3. IF SPACING IS < 5 TIMES BAR DIAMETER, INCREASE LAP LENGTH AND EMBEDMENT SHOWN BY 25%.
- 4. TOP REINFORCING IS HORIZONTAL STEEL SO PLACED THAT MORE THAN 12" OF FRESH CONCRETE IS CAST IN THE MEMBER BELOW THE REINFORCING.

	f'c =	4.0 ksi	fy = 6	0.0 ksi
BAR SIZE	LAP LEN	GTH (IN)	EMBEDMENT	LENGTH (IN)
DAR SIZE	TOP	OTHER	TOP	OTHER
#3	24	18	18	15
#4	33	24	24	19
#5	40	31	31	24
#6	48	38	37	29
#7	70	55	54	42
#8	81	62	62	48
#9	91	70	70	54
#10	103	79	79	61
#11	113	87	87	67



# TYPICAL STIRRUPS & TIES

REINFORCING LAP SCHEDULE





SPLICE OF REINFORCING BARS

1180 Iron Point Rd. Suite 260 Folsom, CA 95630 PH: (916)608-2212 Fax: (916)608-2232 HDR Engineering Inc.




PROFESS/ON	REV	DATE	BY	DESCRIPTION
IN F. DE TE				
(4/2)\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\				
(15/2) (S)(S)				
(일 No. 48214   위)				
\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\				
\\varphi\				
VICIVIL OR				
FOF CALIFOLD	-		-	



SMITH CANAL CLOSURE STRUCTURE
PRELIMINARY DESIGN FOR CONDITIONAL
LETTER OF MAP REVISION


TYPICAL	REINFORCEMENT	DETAILS
IIIIOAL	IVEHAL OLIOCHICIAL	DEIAILO


				SHEE
	SAN JOAQUII	N AREA FLOOD CO	NTROL AGENCY	S-00
1	SCALE: NO SCALE	CHECKED BY:	DATE:	OF
ı	DESIGNED BY: K. DE LAPP			
ı	DRAWN BY: V. RUSSO			XX
ı	CHECKED BY:			
ı	DATE:	SIGNATOR'S NAME, COI	MPANY NAME	SHEET




DATE:

SIGNATOR'S NAME COMPANY NAME








TYPICAL WALL DETAIL AT ROOF


3/16

ROOF METAL DECK




- TRUSS SPACING SHALL BE TYPICALLY 4'-0" OC. THE EMBED PLATE LENGTH & NUMBER OF STUDS TO BE MODIFIED FROM SHOWN IF TRUSS SPACING IS DIFFERENT FROM 4'-0".
- 2. FOR DECK SIZE, WELDING AND PROPERTIES SEE TYPICAL METAL DECK DETAILS.
- 3. FOR EASE OF CONSTRUCTION COORDINATE LOCATION OF STUDS WITH CENTER OF CMU CELL.





- UNLESS OTHERWISE NOTED PER SCHEDULE, PROVIDE MINIMUM OF 2-#5 FOR 8" CMU WALLS AND 2-#6 FOR 12" CMU WALLS.
- 2. 2-#7 IN EACH OF FIRST TWO CELLS.




#### NOTES:

- CONDITION SHOWN FOR TWO LAYERS OF REINFORCEMENT. FOR ONE LAYER CONDITION, HOOK HORIZONTAL BARS AT JOINT AND ELIMINATE BARS.
- NO HORIZONTAL REINFORCEMENT SHALL GO THRU THE JOINT EXCEPT AS SHOWN IN TYPICAL CMU WALL ELEVATION.
- 3. MAXIMUM JOINT SPACING SHALL BE 30'-0", UNLESS NOTED OTHERWISE ON PLANS







FASCIA TUBE DETAILS

REINFORCEMENT SCHEDULE

SHEAR PANEL BOUNDARY



No. 48214

7	REV	DATE	BY	DESCRIPTION
H				
IG NE				
\ <u>E</u>				
[2]				
<u> </u>				
<i>]]</i>				
	_		_	



SMITH CANAL CLOSURE STRUCTURE PRELIMINARY DESIGN FOR CONDITIONAL **LETTER OF MAP REVISION** 

HSS 6x2x3/16"


**TYPICAL BLOCK WALL DETAILS II** 

SAN JOAQUIN AREA FLOOD CONTROL AGENCY						
			]			
SCALE: NO SCALE	CHECKED BY:	DATE:	OF			
DESIGNED BY: K. DE LAPP						
DRAWN BY: V. RUSSO			xx			
CHECKED BY:						
DATE:	SIGNATOR'S NAME,	COMPANY NAME	SHEETS			

PETERSON . BRUSTAD . INC ENGINEERING . CONSULTING

1180 Iron Point Rd. Suite 260 Folsom, CA 95630 PH: (916)608-2212 Fax: (916)608-2232






#### NOTES:

- STEEL SHEET PILING SHALL BE PZ-22 ASTM A572 GRADE 50 OR APPROVED EQUAL WITH DIMENSIONS AND PROPERTIES SHOWN IN TABLE ON THIS SHEET.
- 2. STEEL SHEET PILING SHALL BE CAST HOT ROLLED IN THE U.S.A.
- 3. STEEL SHEET PILING SHALL HAVE BALL AND SOCKET INTERLOCK.
- 4. THE CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

STEEL SHEET PILE DIMENSIONS AND PROPERTIES								
			WEI	GHT	MOMENT	SECTION	COATING	AREA
SECTION	AREA (IN²/FT)	WIDTH (IN)	PER SINGLE (LBS/FT)	PER WALL (LBS/FT²)	OF INERTIA	MODULUS (IN <sup>3</sup> /FT)	PER SINGLE (FT²/FT)	PER WALL (FT²/FT²)
PZ-22	6.47	22	40.3	22	84.38	18.1	4.48	1.22



PZ-22 SECTION	A
NTS	_







REV	DATE	BY	DESCRIPTION	
-				
				San Joaquin R
				}
-		_		




ı	SMITH CANAL CLOSURE STRUCTURE
١	PRELIMINARY DESIGN FOR CONDITIONAL
١	LETTER OF MAP REVISION

TVDIC	AL SHEET	DII E
WALL	SECTION	NO. 1

ı				SHEET
	SAN JOAQUIN AREA FLOOD CONTROL AGENCY			
1	SCALE: NO SCALE	CHECKED BY:	DATE:	OF
ı	DESIGNED BY: K. DE LAPP			
ı	DRAWN BY: V. RUSSO			xx
ı	CHECKED BY:			1
	DATE:	SIGNATOR'S NAME,	COMPANY NAME	SHEETS

IF THIS BAR DOES NOT MEASURE 1" THEN TO SCALE.



PETERSON . BRUSTAD . INC
ENGINEERING . CONSULTING

1180 Iron Point Rd. Suite 260
Folsom, CA 95630
PH: (916)608-2212 Fax: (916)608-2232



STER KE KES	PROFESSION,	S S S S S S S S S S S S S S S S S S S
REGIS	No. 48214 Exp. 6-30-10	VEER
1000	CIVIL FOF CALIFOR	<u> </u>

REV	DATE	BY	DESCRIPTION	
				Son Joogu
				00
-		-		1


	PF
SJAFCA	
San Joaquin Area FLOOD CONTROL Agency	

SMITH CANAL CLOSURE STRUCTURE
PRELIMINARY DESIGN FOR CONDITIONAL
LETTER OF MAP REVISION

CONTROL GATE STRUCTURE FOUNDATION PLAN
--

SAN JOAQUIN AREA FLOOD CONTROL AGENCY				Ç L
SCALE: $3/16" = 1' - 0"$	CHECKED BY:	DATE:	OF	II
DESIGNED BY: K. DE LAPP				ı
DRAWN BY: V. RUSSO			xx	ı
CHECKED BY:				ı
DATE:	SIGNATOR'S NAME, C	OMPANY NAME	SHEETS	ľ
		•	•	•

S-401
S-401
FINS BAR DOES NOT MEASURE 1" THEN



CONTROL GATE STRUCTURE
3/16" = 1'-0"

1

PETERSON . BRUSTAD . INC ENGINEERING . CONSULTING

1180 Iron Point Rd. Suite 260 Folsom, CA 95630
PH: (916)608-2212 Fax: (916)608-2232



KE SE	HF. DE LADO
REGIS	No. 48214 Exp. 6-30-10
18.5	E OF CALIFORNIA


EV	DATE	BA	DESCRIPTION	
				The state of the state of the state of
				Z IUCCU
				וווע וווע
				San Joaquin Fireo FLOOD CONTROL Figency
				1000
-		_		

SMITH CANAL CLOSURE STRUCTURE
PRELIMINARY DESIGN FOR CONDITIONAL
LETTER OF MAP REVISION

CONTROL GATE AND STRUCTURE	
SECTION I	

			SHEET	BAR
SAN JOAQUIN	AREA FLOOD	CONTROL AGENCY	S-402	IF THIS
SCALE: $3/16" = 1' - 0"$	CHECKED BY:	DATE:	OF	I
DESIGNED BY: K. DE LAPP				ı
DRAWN BY: V. RUSSO			xx	П
CHECKED BY:				И
DATE:	SIGNATOR'S NAME,	COMPANY NAME	SHEETS	ı

1. FOR ADDITIONAL INFORMATION SEE SHEETS S-401 & S-402.



CONTROL GATE STRUCTURE

3/16" = 1'-0"






GISTER (CISTER)	PROFESSIONAL FILES
REG	No. 48214 Exp. 6-30-10
No.	CIVIL ORNE

 	 2233111111311	
		CIOCO
		San Joaquin Firea FLOOD CON

SMITH CANAL CLOSURE STRUCTURE PRELIMINARY DESIGN FOR CONDITIONAL
LETTER OF MAP REVISION

CONTROL GATE AND STRUCTURE SECTION II	
--	--

				SHEET
SAN JOAQUIN AREA FLOOD CONTROL AGENCY				S-403
CALE: $3/16" = 1' - 0"$	CHECKED BY:	DATE:		OF
SIGNED BY: K. DE LAPP				
RAWN BY: V. RUSSO				xx
HECKED BY:				
ATE:	SIGNATOR'S NAME,	COMPANY NAME		SHEETS
	•	•		



P-1 P-2 P-3 P-4 P-5 P-6 P-7 P-8 P-9	24"Øx3/4" 24"Øx3/4" 24"Øx3/4" 24"Øx3/4" 24"Øx3/4" 24"Øx3/4" 24"Øx3/4" 24"Øx3/4"	-13.85 -13.85 -13.85 -13.85 -13.85 -13.85	-65.0 -65.0 -65.0 -65.0	NOTES 1,3,4,8,9
P-3 P-4 P-5 P-6 P-7 P-8	24"Øx3/4" 24"Øx3/4" 24"Øx3/4" 24"Øx3/4" 24"Øx3/4"	-13.85 -13.85 -13.85	-65.0	1,5,4,5,5
P-4 P-5 P-6 P-7 P-8	24"Øx3/4" 24"Øx3/4" 24"Øx3/4" 24"Øx3/4" 24"Øx3/4"	-13.85 -13.85 -13.85		
P-5 P-6 P-7 P-8	24"Øx3/4" 24"Øx3/4" 24"Øx3/4" 24"Øx3/4"	-13.85 -13.85	-65.0	
P-5 P-6 P-7 P-8	24"Øx3/4" 24"Øx3/4" 24"Øx3/4"	-13.85		+
P-6 P-7 P-8	24"Øx3/4" 24"Øx3/4"		-65.0	+ + -
P-7 P-8	24"Øx3/4"		-65.0	+ + -
P-8		-13.85	-65.0	+ + -
		-13.85	-65.0	+ + -
	24"Øx3/4"	-13.85	-65.0	+
P-10	24"Øx3/4"	-13.85	-65.0	+
P-11	24"Øx3/4"	-13.85	-65.0	+
P-12	24"Øx3/4"	-13.85	-65.0	+ + -
P-13	24"Øx3/4"	-13.85	-65.0	+ + -
P-14	24"Øx3/4"	-13.85	-65.0	+ + -
P-15	24"Øx3/4"	-13.85	-65.0	+
P-16	24"Øx3/4"	-13.85	-65.0	+ + -
P-17	24"Øx3/4"	-13.85	-65.0	+ + -
P-18	24"Øx3/4"	-13.85	-65.0	+ + -
P-19	24"Øx3/4"	-13.85	-65.0	+
P-20	24"Øx3/4"	-13.85	-65.0	+ + -
P-21	24"Øx3/4"	-13.85	-65.0	+
P-22	24"Øx3/4"	-13.85	-65.0	+ + -
P-23	24"Øx3/4"	-13.85	-65.0	+
P-24	24"Øx3/4"	-13.85	-65.0	+ + -
P-25	24"Øx3/4"	-13.85	-65.0	+
P-26	24"Øx3/4"	-13.85	-65.0	+ + -
P-27	24"Øx3/4"	-13.85	-65.0	
P-28	24"Øx3/4"	-13.85	-65.0	
P-29	24"Øx3/4"	-13.85	-65.0	+ + -
P-30	24"Øx3/4"	-13.85	-65.0	
P-31	24"Øx3/4"	-13.85	-65.0	
P-32	24"Øx3/4"	-13.85	-65.0	
P-33	24"Øx3/4"	-13.85	-65.0	
P-34	24"Øx3/4"	-13.85	-65.0	
P-35	24"Øx3/4"	-13.85	-65.0	
P-36	24"Øx3/4"	-13.85	-65.0	
P-37	24"Øx3/4"	-13.85	-65.0	
P-38	24"Øx3/4"	-13.85	-65.0	
P-39	24"Øx3/4"	-13.85	-65.0	
P-40	24"Øx3/4"	-13.85	-65.0	
P-41	24"Øx3/4"	-13.85	-65.0	
P-42	24"Øx3/4"	-13.85	-65.0	
P-43	24"Øx3/4"	-13.85	-65.0	
P-44	24"Øx3/4"	-13.85	-65.0	
P-45	24"Øx3/4"	-13.85	-65.0	
P-46	24"Øx3/4"	-13.85	-65.0	
P-47	24"Øx3/4"	-13.85	-65.0	
P-48	24"Øx3/4"	-13.85	-65.0	
P-49	24"Øx3/4"	-13.85	-65.0	
P-50	24"Øx3/4"	-13.85	-65.0	
P-51	24"Øx3/4"	-13.85	-65.0	
P-52	24"Øx3/4"	-13.85	-65.0	T 🔻

PILE SCHEDULE (P) (CONT)				
MARK TYPE REFERENCE ELEV "A" (FEET)			TIP ELEV (FEET)	REMARK
P-54	24"Øx3/4"	-13.85	-65.0	NOTES 1,3,4,8,9
P-55	24"Øx3/4"	-13.85	-65.0	
P-56	24"Øx3/4"	-13.85	-65.0	
P-57	24"Øx3/4"	-13.85	-65.0	
P-58	24"Øx3/4"	-13.85	-65.0	
P-59	24"Øx3/4"	-13.85	-65.0	
P-60	24"Øx3/4"	-13.85	-65.0	
P-61	24"Øx3/4"	-13.85	-65.0	
P-62	24"Øx3/4"	-13.85	-65.0	
P-63	24"Øx3/4"	-13.85	-65.0	
P-64	24"Øx3/4"	-13.85	-65.0	
P-65	24"Øx3/4"	-13.85	-65.0	
P-66	24"Øx3/4"	-13.85	-65.0	
P-67	24"Øx3/4"	-13.85	-65.0	
P-68	24"Øx3/4"	-13.85	-65.0	
P-69	24"Øx3/4"	-13.85	-65.0	
P-70	24"Øx3/4"	-13.85	-65.0	
P-71	24"Øx3/4"	-13.85	-65.0	<b>V</b>
P-72	24"Øx3/4"	-13.85	-65.0	NOTES 1,3,4,8,9

#### NOTES:

- 1. "P" DENOTES PILE
- PILES SHALL BE 3/4" IN THICKNESS. MINIMUM LENGTH OF PILES SHALL BE DETERMINED BY THE CONTRACTOR BASED ON SCHEDULED INFORMATION.
- 3. 3'-0" SACRIFICIAL BASE SLAB, SEE S-501 FOR INFO.
- 4. ELEVATION "A" REFER TO BOTTOM OF STRUCTURAL SLAB.
- 5. PROVIDE 8 SUPPORTING 1"0x8" WELDED HEADED STUDS © EQUAL 45' SPACING. CENTERLINE OF STUDS SHALL BE 5" BELOW TOP OF SACRIFICIAL SLAB
- 6. TYPICAL BOTTOM MAT REINF. SEE PLAN AND SECTIONS FOR SIZE AND SPACING. DOUBLE THE FIRST BAR ON EITHER SIDE, EITHER DIRECTION.
- TYPICAL TOP MAT REINF SEE PLAN AND SECTIONS FOR SIZE AND SPACING.
- 8. FOR TYPICAL PILE CONSTRUCTION, SEE DETAIL S-501.
- 9. ALL CIRCULAR PILES SHALL BE FILLED WITH STRUCTURAL CONCRETE / CDF PER DETAIL S-501.
- 10. SEE PLANS FOR ALL TOP OF CONCRETE ELEVATIONS.

PETERSON . BRUSTAD . INC ENGINEERING . CONSULTING 1180 Iron Point Rd. Suite 260 Folsom, CA 95630 PH: (916)608-2212 Fax: (916)608-2232





	REV	DATE	BY	DESCRIPTION
//				
://				
;}}				
?//				
7				
	-		-	



SMITH CANAL CLOSURE STRUCTURE PRELIMINARY DESIGN FOR CONDITIONAL LETTER OF MAP REVISION
PILE SCHEDULES AND DETAILS


SAN JOAQUIN AREA FLOOD CONTROL AGENCY					
SCALE: NO SCALE	CHECKED BY:		DATE:		
DESIGNED BY: K. DE LAPP					
DRAWN BY: V. RUSSO					
CHECKED BY:					
DATE:	SIGNATOR'S I	NAME, COMPANY	NAME		

SHEET

S-50°

XX

SHEETS



S-007 S-007
TYP AT TYP AT JOIST DECK 400 GAL RECIEVER TANK GATE MECHANICAL CABINET INGERSOLL RAND MODEL UP6-25-125TAS WITH AIR DRYER INGERSOLL RAND MODEL UP6-25-125TAS WITH AIR DRYER  $\langle 2 \rangle$ 


CONTROL BUILDING PLAN
1/2" = 1'-0"

# CONTROL BUILDING SECTION 1/2" = 1'-0"

#### NOTES:

- 1'-0"W  $\times$  1'-0"DP CONCRETE FOOTING W/ 2-#5 T&B AND #5 VERT AT 16" OC.  $\langle 1 \rangle$
- $\langle 2 \rangle$ 8" CONCRETE SLAB W/ #5 AT 12" OC EW CENTERED IN SLAB
- 3  $8\ensuremath{^{\prime\prime}}$  CMU, FOR REINFORCEMENT SEE TYPICAL DETAILS, SHEET S-007, MISC LOCATIONS
- $\langle 4 \rangle$ COMPOSITION ROOFING OVER CORRUGATED METAL DECK OVER STEEL BAR JOIST TRUSSES.
- 3'-0" x 3'-0" BACKDRAFT DAMPER W/ LOUVER COVER







ليان	REV	DATE	BY	DESCRIPTION	
\$	$\vdash$				
4 (8)					~
-10 /2//	-				Sor
( OFIX					
150	-		-		



SMITH CANAL CLOSURE STRUCTURE
PRELIMINARY DESIGN FOR CONDITIONAL
LETTER OF MAP REVISION

CONTROL BUILDING MECHANICAL	
PLAN AND SECTION	

			SHEET	
SAN JOAQUIN AREA FLOOD CONTROL AGENCY				
SCALE: 1/2" = 1' - 0"	CHECKED BY:	DATE:	OF	
DESIGNED BY: K. DE LAPP				
DRAWN BY: V. RUSSO			xx	
CHECKED BY:				
DATE:	SIGNATOR'S NAME	, COMPANY NAME	SHEETS	